MATTEI ROTARY VANE AIR COMPRESSOR DATA SHEET - FIXED-SPEED

Model Number:	ERC 4 HX			Date:	2-Jan-2025
Cooling Media:	Air-cooled	Х	Water-cooled		Oil Injection X
Inlet Control Scheme:	Load/No Load	Х	Modulation X		Inverter
Starting System:	Full Voltage		Star-Delta X		Soft-Start

PERFORMANCE SPECIFICATIONS: SPEED, POWER, PRESSURE

Compression Module Rotational Speed	1800	rpm
Nominal Drive Motor Rotational Speed	1800	rpm
Drive Motor Nominal Rating	5	hp
Drive Motor Nominal Efficiency	91.7	percent
Maximum Full Flow Operating Pressure ^c	145	psig ^c
Full Load Operating Pressure b	137	psig b
Fan Motor Nominal Rating (if applicable)	0.25	hp
Fan Motor Nominal Efficiency	n/a	percent

"VANE GAIN" PERFORMANCE EFFICIENCY GAINS OVER TIME⁸

Efficiency Improvement timeline	500	hours
Rated Capacity at Full Load Operating Pressure a	22.0	acfm ^a
Total Package Input Power at Rated Capacity and Full Load Operating Pressure ^d	5.92	kW ^d
Specific Package Input Power at Rated Capacity and Full Load Operating Pressure	26.91	kW/100 cfm
Isentropic Efficiency at Rated Capacity and Full Load Operating Pressure ^f	59.10	Percent of ideal compression
Total Package Input Power at Zero Flow	1.40	Kw

NOTES:

- a. Measured at the discharge terminal point of the compressor package in accordance with ISO 1217, Annex C; ACFM is actual cubic feet per minute at inlet conditions.
- b. The operating pressure at which the Rated Capacity and Total Package Input Power Energy Consumption at Rated Capacity and Full Load Operating Pressure were measured.
- c. Maximum pressure attainable at full flow, usually the unload pressure setting for load/no load control or the maximum pressure attainable before capacity control begins. May require additional power.
- d. Total package input power at other than reported operating points will vary with inlet control scheme.
- f. Isentropic Efficiency: real performance at flow and pressure per ISO 1217 compared to an ideal compression process.
- g. VANE GAIN: Proven efficiency and output performance gains as the blades season through normal operation.

